

FACULTY OF ENGINEERING CHULALONGKORN UNIVERSITY FIRE SAFETY RESEARCH CENTER



TYPE OF TEST

: POSITIVE PRESSURE FIRE TEST OF DOOR ASSEMBLIES

TEST SPECIMEN

"SPR" Steel Fireproof Door with Glass Vision (Size 1000 x 2100 mm)

The specimen is a doorset consisting of single-sided steel door leaf with a vision panel and a steel door frame. The dimensions of the door leaf are 2054 mm x 925 mm x 45 mm. The door leaf has a fixed 127 mm x 508 mm Pyran clear fire rated glass (9 mm) vision panel located at the height of 1246 mm measured from its lower edge. The door leaf is constructed of 1.5-mm thick cold rolled steel sheet in-filled with rock wool with a density of 100 kg/m³. The specimen was mounted in a 15-cm thick reinforced concrete wall, which was installed on the 3.5 m x 3.5 m testing frame, such that the door opened into the furnace chamber. The door leaf was locked with the door frame by a door knob (Fire Mortise Lock), and 5 stainless steel hinges. Smoke rubber seal was installed around the edge of the door frame. The details of the specimen are shown in Appendix C. The specimen was provided and installed by the client.

CLIENT

: SUPA RICH CO., LTD.

27 Ramintra Soi 48, Ramintra Road, Kannayao

Kannayao, Bangkok 10230, Thailand

DATE OF TEST

: December 22, 2017

TEST MACHINE

Large-scale vertical furnace at the Fire Safety Research Center (FSRC), Department of Civil Engineering, Chulalongkorn University in Saraburi province, Thailand. The furnace is capable of producing a standard temperature-time relationship according to several fire resistance standards including UL 10C.

TEST METHOD

The testing procedures follow UL 10C: Positive pressure fire tests of door assemblies

for a desired fire rating of 3:00 hr.

TEST RESULTS

: The test assembly described above has withstood the fire endurance classification period and hose-stream test as stated in the table below:

(The test results are good only for the specimen tested.)

Criteria	Fire Resistance (hr:min)	Remarks
Integrity	3:00	No flaming occurred on the unexposed surface of the door for the fire test duration of 180 minutes.
Hose Stream Test	Passed	 No portion of the door edges adjacent to the door frame moved from the original position greater than 1½ times the door thickness as a result of the hose stream test. The latch bolt remained projected and intact after the test. The door frame remained securely fastened to the wall on all sides.

Date: January 5, 2018

Tested by:

(Associate Prof. Dr. Thanyawat Pothisiri)


(Associate Prof. Dr. Tirawat Boonyatee)
On Behalf of Head of Civil Engineering Department



FACULTY OF ENGINEERING CHULALONGKORN UNIVERSITY FIRE SAFETY RESEARCH CENTER



FURNACE TEMPERATURE



- Average Furnace Temperature

-UL 10C

-Specimen Temperature

(Mr. Sirichai Pethrung)
Authorized Testing Officer